



FLOOR CONTROL PAK

MODEL LVFCPAK



FEATURES:

- Preassembled for ease of installation
- All parts are UL Listed and FM Approved
- Can be supplied with test and drain or ball valve as required
- Butterfly valve has built in tamper switch
- Easily field serviced
- Sizes: 2, 2½", 3", 4", 6", 300 PSI
- Test and drain with optional PRV, available nominal K-Factor: 2.8, 4.2, 5.6, 8.0, 11.2, 14.0 (available on 1-1/4" - 2" size units only), and 25.2 (available on 1-1/2" and 2" size units only)

SIZE (In.)	OVERALL LENGTH (In.)	OVERALL DEPTH (In.)
2	18	12
2-1/2	18	13.3
3	18	14
4	18	16
6	19	19.5

PROJECT	APPROVAL STAMP
PROJECT:	<input type="checkbox"/> APPROVED
ADDRESS:	<input type="checkbox"/> APPROVED AS NOTED
ENGINEER:	<input type="checkbox"/> NOT APPROVED
SUBMITTAL DATA:	REMARKS:
NOTES 1:	
NOTES 2:	